| HIDE-FAST SL 24 | | |
|---|---|----------------------|
| SPRING LOCK COPING, 1/4" SLOPE ROOF MEMBRANE SPLICE PLATES 6" WIDE 1/2" 1/2" 1/2" 4" 3-1/2" 3" CLIP TO BE FABRICATED 3/8" LARGER THAN WALL SIZE FOR WALL VARIATION AND TO FACILITATE INSTALLATION | | |
| Continuous Cleat and fasteners provided. Concealed Splice Plates provided. Splice Plate Sealant available for extra charge. | Outside Miters**. Optional Welded | |
| PRINT APPROVAL: Architect and/or Contractor shall verify all dimensions, sizes, and quantities, All products to be installed in strict accordance with TSM's printed instructions. Approved By: | Inside Miters**: Optional Welded (Surcharge Appli Right End Caps**: Optional Welded (Surcharge Appli Left End Caps**: Optional Welded (Surcharge Appli Splice Plate Tape Sealant: Optional Sealant (Surcharge Appli | ies) ies) ies) |
| Date: PROJECT: | ** Standard riveted | |
| ARCHITECT: | | - I |
| ROOFING CONTRACTOR: | 240A040 AL | |
| REPRESENTATIVE: | Finish: | |
| TRI-STATE METALS41 North Lawn Ave / Elms Ph. 914-347-6 Web: www.tsmn email: sales@tsm | sford, NY 10523 ⁸¹⁵⁷ ⁸¹⁹¹ ^{hy.com} Color: Effective Date: 8/8/17 Drawn By: B Z M | |